

2.05 UNDERGROUND PIPING

- A. All underground piping shall be fusion welded HDPE.
TRACER WIRE IS REQUIRED FOR ALL UNDERGROUND PIPING

PART 3 EXECUTION

3.01 TESTING:

- A. Natural gas piping shall be tested in accordance with International Fuel Gas Code requirements.
- B. SHSU REQUIRES A 4 HOUR TEST WITH A CERTIFIED DIAPHRAGM GAUGE. LOW